

Quality Engineering Test Report

SERIES: SD-150B 150W DC-DC SINGLE OUTPUT SWITCHING POWER SUPPLY

SAMPLE: A. SD-150B-12 12V / 12.5A

B. SD-150B-24 24V / 6.3A

NO	TEST ITEM	TEST CONDITION / SPECIFICATION	RESULT	VERDICT
1	DC INPUT VOLTAGE RANGE	I/P : TESTING SPEC : 19~36VDC O/P : FULL LOAD	B: 16.1~36VDC	P
2	LINE REGULATION	I/P : 19~36VDC SPEC : A:±0.5% O/P : FULL LOAD B:±0.3%	A: -0%~+0% B: -0%~+0%	P
3	LOAD REGULATION	I/P : 24VDC SPEC : A:±0.5% O/P : MIN. TO FULL LOAD B:±0.3%	A: -0.1%~+0.1% B: -0.05%~+0.05%	P
4	OUTPUT VOLTAGE TOLERANCE	I/P : 19~36VDC SPEC : A:±1% O/P : MIN. TO FULL LOAD B:±1%	A: -0.1%~+0.2% B: -0.05%~+0.08%	P
5	RIPPLE&NOISE	I/P : 24VDC SPEC : A:120mVp-p O/P : FULL LOAD B:150mVp-p	A: 19mV B: 16mV	P
6	DC INPUT CURRENT	I/P : 24VDC SPEC : 8.5A O/P : FULL LOAD	B: 7.6A	P
7	MAX. INRUSH CURRENT	I/P : 24VDC SPEC : NONE O/P : FULL LOAD	B: 49.3A	P
8	O/P VOLTAGE ADJ. RANGE	I/P : 24VDC SPEC : A:11~16V O/P : MIN. LOAD B:23~30V	A: 9.71~16.61V B: 21.73~33.03V	P
9	SET UP TIME	I/P : 24VDC SPEC : 2S O/P : FULL LOAD	B: 1632mS	P
10	EFFICIENCY	I/P : 24VDC SPEC : A:75% O/P : FULL LOAD B:77%	A: 77.2% B: 81.4%	P
11	OVER LOAD PROTECTION	I/P : 24VDC SPEC : 105%~135% O/P : TESTING	A: 121% B: 120.8%	P
12	OVER VOLTAGE PROTECTION	I/P : 24VDC SPEC : A:16.8V~20V O/P : TESTING B:31.5V~37.5V	A: 17.78V B: 34.99V	P
13	INSULATION RESISTANCE	SPEC : I/P-O/P : 500VDC/100M Ohms MIN. I/P-FG : 500VDC/100M Ohms MIN. O/P-FG : 500VDC/100M Ohms MIN.	B: I/P-O/P : >100M Ohms I/P-FG : >100M Ohms O/P-FG : >100M Ohms	P
14	DIELECTRIC / WITHSTAND VOLTAGE	SPEC : I/P-O/P : 1500VAC/ 1 min (10mA CUT-OFF). I/P-FG : 1500VAC/ 1 min (10mA CUT-OFF) O/P-FG : 500VAC/ 1 min (10mA CUT-OFF)	B: I/P-O/P : <3.77mA I/P-FG : <4.72mA O/P-FG : <3.36mA	P
15	BURN-IN TEST	I/P : 24VDC O/P:FULL LOAD TA : 27.4°C BURN-IN DURATION : 4 hrs	B:NON BREAK	P
16	ENVIRONMENT TEST (SAMPLE A:)	1.LOW TEMPERATURE TEST I/P : 18.3 VDC O/P : FULL LOAD AMBIENT TEMPERATURE : -10°C	AFTER 2 hrs POWER ON OK	P
		2.HIGH AMBIENT TEMPERATURE FULL LOAD TEST I/P : 24.1VDC O/P : FULL LOAD AMBIENT TEMPERATURE : 27.4°C	AFTER 3 hrs NON BREAK	

NO	TEST ITEM	TEST CONDITION / SPECIFICATION	RESULT	VERDICT																												
17	TEMPERATURE RISE TEST T rise OF PARTS	B: I/P : 24VDC AFTER 1 hr BURN-IN O/P : FULL LOAD TA : 22.4°C <table><tr><th>POSITION</th><th>P/N</th><th>TEMP</th><th>T rise</th></tr><tr><td>Q1</td><td>MAIN TRANSISTOR</td><td>92.8°C</td><td>69.1°C</td></tr><tr><td>T1</td><td>MAIN TRANSFORMER</td><td>76.1°C</td><td>52.4°C</td></tr><tr><td>D11</td><td>O/P DIODE</td><td>80.5°C</td><td>56.8°C</td></tr><tr><td>C33</td><td>O/P FILTER CAPACITOR</td><td>55°C</td><td>31.3°C</td></tr><tr><td>L1</td><td>O/P CHOCK</td><td>62.2°C</td><td>38.5°C</td></tr><tr><td>C5</td><td>I/P FILTER CAPACITOR</td><td>53.7°C</td><td>30°C</td></tr></table>	POSITION	P/N	TEMP	T rise	Q1	MAIN TRANSISTOR	92.8°C	69.1°C	T1	MAIN TRANSFORMER	76.1°C	52.4°C	D11	O/P DIODE	80.5°C	56.8°C	C33	O/P FILTER CAPACITOR	55°C	31.3°C	L1	O/P CHOCK	62.2°C	38.5°C	C5	I/P FILTER CAPACITOR	53.7°C	30°C		P
POSITION	P/N	TEMP	T rise																													
Q1	MAIN TRANSISTOR	92.8°C	69.1°C																													
T1	MAIN TRANSFORMER	76.1°C	52.4°C																													
D11	O/P DIODE	80.5°C	56.8°C																													
C33	O/P FILTER CAPACITOR	55°C	31.3°C																													
L1	O/P CHOCK	62.2°C	38.5°C																													
C5	I/P FILTER CAPACITOR	53.7°C	30°C																													
18	LIFE CYCLE	B: SUPPOSE C33 IS THE MOST CRITICAL COMPONENT I/P : 24VDC O/P : FULL LOAD Ta : 25°C Tc33 : 56.3°C Life: 45941 hrs I/P : 24VDC O/P : FULL LOAD Ta : 34°C Tc33 : 66.7°C Life: 23291 hrs		P																												
19	CRITICAL COMPONENT RECORD (FOR QC INSPECTION REFERENCE ONLY)	B: FUSE : F 15AL/250V G UL INPUT DIODE : 1N5401 LINE FILTER : LF TF-307-R1 EE-35 TRANSFOMER : MT TF-300-R1 ETD-34 POWER SWITCHER : C25P06Q TO-3P OUTPUT DIODE : D9202 TO-3P OUTPUT CAPACITOR : JAMICON 330uF/50V 105°C WG INPUT CAPACITOR : N.C.C 330uF/100V KMF 105°C P.C.B : SD-150-R1 FR-4 2 OZ DS																														
DATE	SAMPLE	TEST RESULT	TEST	APPROVAL																												
980506	SD-150B	PASS	H.C.LIOU	Max Lin																												