



# TEST REPORT: EPS-45S-48

## 45W Single Output Switching Power Supply

### ■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

### ■ SAFETY & E.M.C. TEST



Safety Test

E.M.C. Test


### ■ RELIABILITY TEST

ENVIRONMENT TEST


# DESIGN VERIFY TEST OUTPUT FUNCTION

| NO | TEST ITEM                      | SPECIFICATION                                                                                          | TEST CONDITION                                              | RESULT                             |
|----|--------------------------------|--------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|------------------------------------|
| 1  | OUTPUT VOLTAGE ADJUST RANGE    | CH1: 45.60V ~ 52.80V                                                                                   | I/P : 230VAC<br>O/P: MIN LOAD<br>TA : 25°C                  | CH1: 43.97V ~ 53.94V               |
| 2  | OUTPUT VOLTAGE TOLERANCE (Max) | V1 : 1.0% ~ -1.0%                                                                                      | I/P : 115VAC / 264VAC<br>O/P: FULL / MINLOAD<br>TA= 25°C    | V1: 0.14% ~ -0.28%                 |
| 3  | LINE REGULATION (MAX.)         | V1 : 0.5% ~ -0.5%                                                                                      | I/P : 115VAC / 264VAC<br>O/P: FULL LOAD<br>TA : 25°C        | V1: 0.06% ~ -0.02%                 |
| 4  | LOAD REGULATION (MAX.)         | V1 : 1.0% ~ -1.0%                                                                                      | I/P : 230VAC<br>O/P: MIN LOAD ~ FULL LOAD<br>TA : 25°C      | V1: 0.14% ~ -0.28%                 |
| 5  | OVER/UNDERSHOOT TEST           | < ±5%                                                                                                  | I/P : 230VAC<br>O/P: FULL LOAD<br>TA : 25°C                 | TEST< 3.361 %                      |
| 6  | RIPPLE & NOISE(Max)            | V1 : 300 mVp-p                                                                                         | I/P : 230VAC<br>O/P: FULL LOAD<br>TA : 25°C                 | V1 : 50.8 mVp-p                    |
|    |                                | high frequency :<br> |                                                             |                                    |
|    |                                | low frequency :<br> |                                                             |                                    |
| 7  | SET UP TIME (MAX.)             | 230VAC : 500ms<br>115VAC : 500ms                                                                       | I/P : 230VAC<br>I/P : 115VAC                                | 230VAC : 96ms<br>115VAC : 70ms     |
|    |                                | INPUT=230VAC/50HZ @ FULL LOAD<br>CH1 : Output Voltage CH2 : AC Input Voltage                           |                                                             |                                    |
|    |                                | INPUT=115VAC/60HZ @ FULL LOAD<br>CH1 : Output Voltage CH2 : AC Input Voltage                           |                                                             |                                    |
|    | RISE TIME (MAX.)               | 230VAC : 30ms<br>115VAC : 30ms                                                                         | I/P : 230VAC<br>I/P : 115VAC<br>O/P: FULL LOAD<br>TA : 25°C | 230VAC : 13.6ms<br>115VAC : 15.4ms |

INPUT=230VAC/50HZ @ FULL LOAD  
CH1 : Output Voltage




INPUT=115VAC/60HZ @ FULL LOAD  
CH1 : Output Voltage




HOLD UP TIME (TYP.)

|        |        |                |        |          |
|--------|--------|----------------|--------|----------|
| 230VAC | : 30ms | I/P : 230VAC   | 230VAC | : 66.4ms |
| 115VAC | : 12ms | I/P : 115VAC   | 115VAC | : 23.2ms |
|        |        | O/P: FULL LOAD |        |          |
|        |        | TA : 25°C      |        |          |

INPUT=230VAC/50HZ @ FULL LOAD  
CH1 : Output Voltage CH2 : AC Input Voltage



INPUT=115VAC/60HZ @ FULL LOAD  
CH1 : Output Voltage CH2 : AC Input Voltage





DYNAMIC LOAD




|                 |                                |             |         |            |
|-----------------|--------------------------------|-------------|---------|------------|
| V1 : 4800 mVp-p | I/P : 230VAC                   | (1).        | (2).    | unit:mVp-p |
|                 | O/P:                           |             |         |            |
|                 | (1)Full/Min load 50%duty/120HZ | V1: 174.0mv | 228.0mv |            |
|                 | (2)Full/Min load 50%duty/1KHZ  |             |         |            |
|                 | TA : 25°C                      |             |         |            |

FULL /50% LOAD 50%DUTY / 120HZ

FULL /50% LOAD 50%DUTY / 1KHZ



## INPUT FUNCTION TEST

| NO                                                                                                                                                                                                                                                                                                                                                                                                           | TEST ITEM                 | SPECIFICATION                                                                    | TEST CONDITION                                                                                                                                                                            | RESULT                                   |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|----------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------|
| 1                                                                                                                                                                                                                                                                                                                                                                                                            | INPUT VOLTAGE RANGE       | 80VAC ~ 264VAC                                                                   | I/P : TESTING<br>O/P : FULL LOAD<br>Ta : 25°C<br><br>I/P :<br>LOW-LINE = 77VAC<br>HIGH-LINE = 300VAC<br>O/P : FULL/MIN LOAD<br>ON:30 Sec ; OFF:30 Sec 10MIN<br>( POWER ON/OFF NO DAMAGE ) | 64.5VAC ~ 264VAC<br><br>TEST : OK        |
| 2                                                                                                                                                                                                                                                                                                                                                                                                            | INPUT FREQUENCY RANGE     | 47HZ ~ 63HZ<br>NO DAMAGE                                                         | I/P : 115VAC ~ 264VAC<br>O/P : FULL-MIN LOAD<br>Ta : 25°C                                                                                                                                 | TEST : OK                                |
| 3                                                                                                                                                                                                                                                                                                                                                                                                            | INPUT CURRENT (TYP.)      | 1 / 230VAC<br>1.2 / 115VAC                                                       | I/P : 230VAC<br>I/P : 115VAC<br>O/P : FULL LOAD<br>TA : 25°C                                                                                                                              | I= 0.418 / 230VAC<br>I= 0.693 / 115VAC   |
| 4                                                                                                                                                                                                                                                                                                                                                                                                            | LEAKAGE CURRENT           | < 0.25mA                                                                         | I/P : 264VAC<br>O/P : MIN LOAD<br>TA : 25°C                                                                                                                                               | L-FG: 0.083 mA<br>N-FG: 0.084 mA         |
| 5                                                                                                                                                                                                                                                                                                                                                                                                            | NO LOAD POWER CONSUMPTION | < 0.10W                                                                          | I/P : 230VAC<br>O/P : MIN LOAD<br>TA : 25°C                                                                                                                                               | < 0.0907 W                               |
| 6                                                                                                                                                                                                                                                                                                                                                                                                            | EFFICIENCY (TYP.)         | 91.0%                                                                            | I/P : 230VAC<br>O/P : FULL LOAD<br>TA : 25°C                                                                                                                                              | 91.22 %                                  |
|                                                                                                                                                                                                                                                                                                                          |                           |                                                                                  |                                                                                                                                                                                           |                                          |
| 7                                                                                                                                                                                                                                                                                                                                                                                                            | INRUSH CURRENT (TYP.)     | 60A / 230VAC<br>30A / 115VAC<br>twidth= 0 us measured at 50% Ipeak<br>COLD START | I/P : 230VAC<br>I/P : 115VAC<br>O/P : FULL LOAD<br>TA : 25°C                                                                                                                              | I= 27.20A / 230VAC<br>I= 27.20A / 115VAC |
| <div> <div> <p>INPUT=230VAC/50HZ @ FULL LOAD</p> <p>CH2 : Input current (1V=1A) CH4 : AC Input Voltage</p>  </div> <div> <p>INPUT=115VAC/50HZ @ FULL LOAD</p> <p>CH2 : Input current (1V=1A) CH4 : AC Input Voltage</p>  </div> </div> |                           |                                                                                  |                                                                                                                                                                                           |                                          |



## PROTECTION FUNCTION TEST

| NO | TEST ITEM               | SPECIFICATION                          | TEST CONDITION                                                        | RESULT                                                                   |
|----|-------------------------|----------------------------------------|-----------------------------------------------------------------------|--------------------------------------------------------------------------|
| 1  | OVER LOAD PROTECTION    | 115% ~ 150%                            | I/P: 264VAC<br>I/P: 230VAC<br>I/P: 115VAC<br>O/P: TESTING<br>Ta: 25°C | 132.5% 264VAC<br>138.9% 230VAC<br>135.6% 115VAC<br>Hiccup Mode           |
| 2  | OVER VOLTAGE PROTECTION | 55.20V ~ 64.80V                        | I/P: 264VAC<br>I/P: 230VAC<br>I/P: 80VAC<br>O/P: MIN LOAD<br>Ta: 25°C | 59.20V 264VAC<br>59.20V 230VAC<br>59.20V 80VAC<br>Shut down Re- power ON |
| 3  | SHORT PROTECTION        | SHORT EVERY OUTPUT<br>1 HOUR NO DAMAGE | I/P: 264VAC<br>I/P: 80VAC<br>O/P: FULL LOAD<br>Ta: 25°C               | NO DAMAGE<br>Hiccup Mode                                                 |

## COMPONENT STRESS TEST

| NO | TEST ITEM            | SPECIFICATION                         | TEST CONDITION                                                                                                            | RESULT                                                                        |
|----|----------------------|---------------------------------------|---------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------|
| 1  | PWM Power Transistor | Q1 Rated : 600V 9.0A                  | I/P : 267VAC<br><br>VDS :<br>O/P : (1)Full Load Turn on<br>(2) Output Short<br>(3)Full load continue<br>Ta : 25°C         | VIN: 267VAC<br>VDS:<br>(1). 552.00V<br>(2). 484.00V<br>(3). 564.00V           |
| 2  | Input Capacitor      | C5 Rated : 100uf 400V                 | I/P : 267VAC<br>O/P : (1)Full Load Turn on /Off<br>(2)Min load Turn on /Off<br>(3)Full Load /Min load Change<br>Ta : 25°C | (1). 360.00V<br>(2). 364.00V<br>(3). 368.00V                                  |
| 3  | Control IC           | U1 Rated : 28.0V (max)<br>-0.3V (min) | I/P : 267VAC<br>O/P : (1)Full Load<br>(2)Output Short<br>(3)O.L.P<br>(4)O.V.P<br>(5)Low Line No Load Vo(min)<br>Ta : 25°C | U1<br>(1). 21.20V<br>(2). 11.20V<br>(3). 20.40V<br>(4). 25.80V<br>(5). 20.20V |
| 4  | O/P Diode            | D100 Rated : 300V 20.0A               | I/P : 267VAC<br>O/P : (1)Full Load Turn on<br>(2) Output Short<br>(3)Full load continue<br>Ta : 25°C                      | (1). 176.00V<br>(2). 164.00V<br>(3). 178.00V                                  |
| 5  | Clamp Diode          | D5 Rated : 800V 2.0A                  | I/P : 267VAC<br>O/P : (1)Full load continue<br>Ta : 25°C                                                                  | (1). 520.00V                                                                  |

## SAFETY &amp; E.M.C. TEST

## SAFETY TEST

| NO | TEST ITEM            | SPECIFICATION            | TEST CONDITION                       | RESULT                       |
|----|----------------------|--------------------------|--------------------------------------|------------------------------|
| 1  | WITHSTAND VOLTAGE    | I/P-O/P : 3.000KVAC /min | I/P-O/P: 3.300KVAC /min<br>Ta : 25°C | I/P-O/P: 1.40mA<br>NO DAMAGE |
| 2  | ISOLATION RESISTANCE | I/P-O/P : 500VDC>100MΩ   | I/P-O/P: 500VDC<br>Ta : 25°C/70%RH   | I/P-O/P: 9999MΩ<br>NO DAMAGE |

## E.M.C. TEST

| NO | TEST ITEM | SPECIFICATION          | TEST CONDITION                                     | RESULT |
|----|-----------|------------------------|----------------------------------------------------|--------|
| 1  | HARMONIC  | EN61000-3-2<br>CLASS A | I/P : 230VAC /50HZ<br>O/P : FULL LOAD<br>Ta : 25°C | PASS   |

|   |            |                                                 |                                                               |                               |
|---|------------|-------------------------------------------------|---------------------------------------------------------------|-------------------------------|
| 2 | CONDUCTION | EN55022<br>CLASS B                              | I/P : 230VAC /50HZ<br>O/P : FULL LOAD / 50% LOAD<br>Ta : 25°C | PASS<br>Test by certified Lab |
| 3 | RADIATION  | EN55022<br>CLASS B                              | I/P : 230VAC /50HZ<br>O/P : FULL LOAD<br>Ta : 25°C            | PASS<br>Test by certified Lab |
| 4 | E.S.D      | EN61000-4-2<br>INDUSTRY AIR: 8KV / Contact: 4KV | I/P : 230VAC /50HZ<br>O/P : FULL LOAD<br>Ta : 25°C            | CRITERIA A                    |
| 5 | E.F.T      | EN61000-4-4<br>INDUSTRY INPUT: 2KV              | I/P : 230VAC /50HZ<br>O/P : FULL LOAD<br>Ta : 25°C            | CRITERIA A                    |
| 6 | SURGE      | IEC61000-4-5<br>INDUSTRY L-N: 2KV;L/N-PE: 4KV   | I/P : 230VAC /50HZ<br>O/P : FULL LOAD<br>Ta : 25°C            | CRITERIA A                    |

## RELIABILITY TEST

| NO | TEST ITEM                                              | SPECIFICATION                                                 | TEST CONDITION                                                    | RESULT             |                        |
|----|--------------------------------------------------------|---------------------------------------------------------------|-------------------------------------------------------------------|--------------------|------------------------|
| 1  | TEMPERATURE RISE TEST                                  | MODEL : EPS-45S-7.5                                           |                                                                   |                    |                        |
|    |                                                        | 1. ROOM AMBIENT BURN-IN : 1.0hrs                              |                                                                   |                    |                        |
|    |                                                        | IP: 230VAC O/P: 100% LOAD TA= 31.3℃                           |                                                                   |                    |                        |
|    |                                                        | 2. HIGH AMBIENT BURN-IN : 1.0hrs                              |                                                                   |                    |                        |
|    |                                                        | IP: 230VAC O/P: 100% LOAD TA= 44.6℃                           |                                                                   |                    |                        |
|    |                                                        | NO.                                                           | Position                                                          | ROOM AMBIENT 31.3℃ | HIGH AMBIENT Ta: 44.6℃ |
|    |                                                        | 1                                                             | LF1                                                               | 47.1℃              | 61.5℃                  |
|    |                                                        | 2                                                             | LF2                                                               | 46.4℃              | 59.4℃                  |
|    |                                                        | 3                                                             | BD1                                                               | 70.2℃              | 83.4℃                  |
|    |                                                        | 4                                                             | Q1                                                                | 76.3℃              | 89.5℃                  |
|    |                                                        | 5                                                             | C5                                                                | 56.0℃              | 69.6℃                  |
|    |                                                        | 6                                                             | C40                                                               | 65.4℃              | 79.4℃                  |
|    |                                                        | 7                                                             | T1                                                                | 68.1℃              | 79.5℃                  |
|    |                                                        | 8                                                             | D100                                                              | 90.6℃              | 103.7℃                 |
|    |                                                        | 9                                                             | C105                                                              | 70.0℃              | 82.3℃                  |
| 2  | OVER LOAD BURN-IN TEST                                 | NO DAMAGE                                                     | I/P : 230VAC                                                      | TEST : OK          |                        |
|    |                                                        | 1 HOUR ( MIN )                                                | O/P : 132% LOAD                                                   |                    |                        |
|    |                                                        |                                                               | Ta : 25℃                                                          |                    |                        |
|    |                                                        |                                                               |                                                                   |                    |                        |
| 3  | LOW TEMPERATURE TURN ON TEST                           | NO DAMAGE<br>1 HOUR ( MIN )                                   | I/P : 264VAC / 115VAC<br>O/P : FULL LOAD<br>Ta : -30.0℃           | TEST : OK          |                        |
| 4  | HIGH HUMIDITY<br>HIGH TEMPERATURE<br>HIGH VOLTAGE TEST | AFTER 12 HOURS<br>IN CHAMBER ON<br>CONTROL 50℃<br>NO DAMAGE   | I/P : 272VAC<br>O/P : FULL LOAD<br>Ta : 50℃<br>HUMIDITY= 95.0% RH | TEST : OK          |                        |
| 5  | TEMPERATURE COEFFICIENT                                | ±0.03% /℃(0~50℃)                                              | I/P : 230VAC<br>O/P : FULL LOAD                                   | ±0.0100% /℃(0~50℃) |                        |
| 6  | STORAGE TEMPERATURE TEST                               | 1. Thermal shock Temperature : -40℃ ~ +85℃                    |                                                                   | TEST : OK          |                        |
|    |                                                        | 2. Temperature change rate : 25℃ / MIN                        |                                                                   |                    |                        |
| 7  | THERMAL SHOCK TEST                                     | 3. Dwell time low and high temperature : 30 MIN/EACH          |                                                                   | TEST : OK          |                        |
|    |                                                        | 4. Total test cycle : 5 CYCLE                                 |                                                                   |                    |                        |
|    |                                                        | 5. Input/Output condition : STATIC                            |                                                                   |                    |                        |
|    |                                                        | 1. Thermal shock Temperature : -35℃ ~ +55℃                    |                                                                   |                    |                        |
|    |                                                        | 2. Temperature change rate : 25℃ / MIN                        |                                                                   |                    |                        |
|    |                                                        | 3. Dwell time low and high temperature : 30 MIN/EACH          |                                                                   | TEST : OK          |                        |
|    |                                                        | 4. Total test cycle : 10 CYCLE                                |                                                                   |                    |                        |
|    |                                                        | 5. Input/Output condition :                                   |                                                                   |                    |                        |
|    |                                                        | 230VAC Full Load AC ON/OFF test turn on 58sec ; turn off 2sec |                                                                   |                    |                        |
|    |                                                        | 1 Carton & 1 Set<br>(1) Waveform : Sine Wave                  |                                                                   | TEST : OK          |                        |



|    |                              |                                                                                                                                                                                                                                                                                |                                                                               |
|----|------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------|
| 8  | VIBRATION TEST               | (2) Frequency : 10~500Hz<br>(4) Acceleration : 2G<br>(5) Test Time : 60min in each axis (X.Y.Z)<br>(6) Ta : 25°C                                                                                                                                                               |                                                                               |
| 9  | CAPACITOR LIFE CYCLE         | :SUPPOSE C105 IS THE MOST CRITICAL COMPONENT<br>(1) I/P : 230VAC O/P : FULL LOAD Ta= 25.0°C LIFE TIME<br>(2) I/P : 230VAC O/P : FULL LOAD Ta= 50.0°C LIFE TIME<br>(3) I/P : 230VAC O/P : 75% LOAD Ta= 50.0°C LIFE TIME<br>(4) I/P : 230VAC O/P : 50% LOAD Ta= 50.0°C LIFE TIME | (1). 104779.8 HRS<br>(2). 19866.9 HRS<br>(3). 51275.1 HRS<br>(4). 97762.8 HRS |
| 10 | MTBF                         | MIL-HDBK-217F<br>TOTAL FAILURE RATE : 726.2 KHRS                                                                                                                                                                                                                               |                                                                               |
| 11 | DMTBF /Accelerated Life test | Demonstration Mean Time Between Failure (Expected Life): Above 50000HRS @ TA 50°C                                                                                                                                                                                              |                                                                               |

|             |        |        |          |
|-------------|--------|--------|----------|
| TEST RESULT | TESTER | REVIEW | APPROVAL |
| PASS        | FRANK  | GESG   | WANGDZ   |

2007/3/20 A50-S014